INDU-ZERO

First productdesigns for Dutch housing associations

Presented by Tom Evers & Rutger Vrielink





Program

- 1. Introduction
- 2. INDU-ZERO background and goals
- 3. Productdesign for the Dutch housing associations
- 4. Showcases
- 5. Next steps



Introduction



Industrial design







Tom Evers D'Andrea & Evers Design



Feel at home!



- Housing association
- Eastern Netherlands
- 15,500 Social homes
- 400 sustainable renovations a year
- Investment: 12 mln a year



Rutger Vrielink
Manager Strategy & Innovation



INDU-ZERO



uropean Regional Development Fund EURC

Starting points project INDU-ZERO

- 1. € 40.000 for zero on the meter renovations performance based
- 2. 15,000 renovation packages per year per factory
- 3. Factory investment around € 200 million



Main steps in the project

- 1. Assessment of the housing stock
- 2. Development of the renovation packages
- 3. Development of the factory blueprint
- 4. VR and AR visualization
- 5. Showcases



Development of the renovation packages



Low Cost

- Less labour on site
- Improving integration of functionality
- Efficient transportation
- In the factory: less time-consuming + less manual labour
- Using low cost materials

Sustainable

- Good insulation
- Smart solutions connecting points panels (no airgaps, thermal bridge, etc)
- Using less different types materials
- Focus on reusability
- Circulair end of life





Cost saving by implementing smart solutions in production process.




Opportunities to innovate and implement features into the panel

- Windows & doors without frame
- Implemention channels for air and conduit
- Implementation of heating system
- Implementation of rain drainage and downspout
- Mounting implementation for PV Panels
- Connection wall with roof



CURRENT RC PANEL



IMPROVE

- Customization through 3D scanning, 3D CAD engineering, 3D milling

North Sea Region

opean Regional Development Fund EUROPEAN UNION


- Integration of all functionalities (construction, electricity, air, water, windows)
- Use less different materials and production steps

Panel / Section construction

CONCEPT 1

Chop spray:

- Polyester glasfiber spray
- Done by robot.
- Strenght needs to be tested
- Polyester spray will react with the EPS, so we need an extra barier layer. Or we can use Epoxy (is more expensive than Polyester)
- Fire resistant is good.
- Production challanges need to be investigated (PolySolv, etc)






Panel / Recycle

Recycle possibilitie

- 1. Reuse the material in the same production proces
- 2. Easy to seperate materials
- Mill out edges
- Peal off hard material





Wood

d Plastic













Stone



Stucco





Windows & Doors



Window frame / Classic










Window frame / Modern











Window / Construction



Modern look Classic Look



Door / Construction











Window Mounted and fixated with frame screwed in insert block






finish frame including window sill





Mounting of the door






End result / Framing - extra cost







Implementation conduits, ventilation and heating












Panel / Build in Heating



Decentral ventilation

- Less problems of mold, no filter problems
- Less connection problems (les airgaps)
- Higher efficienty towards central ventilation
- Better air quality
- No fine dust through ionisation process

Heating

- Electrical heating element
- Heatpump
- City heating

Cooling

- Passive cooling
- Airco, active cooling



Panel / Build in Heating



Enough electricity

- Because of we have the whole roof with solar panels we have enough power for the heating elements, ventilation and hot water ("flowheater").
- This needs more research and calculation.





Panel / Build in Heating



Heating + ventilation

- Electrical heating element
- 5 DCU units pro house
- IR bathroom,
- Hot water with flowheater
- Bathroom and toilet conventional ventilation


















PV Integration into panel

- PV panel mounting
- PV panel ventilation
- Rain wall drainage
- Rain gutter



Remove all the rooftiles




Roof / unknown

several of the current renovation packages partially or fully remove the old roof to have a good surface to mount their renovation package.

In this example new wood is used to space out the old construction





One inherent issue with the roofs that need renovation is that they are most likely not straight (in respect to their outer walls) Usually through weigth and warpage over time the roofs have sunken (concave) in or warped (wavy). Also the (counter)battens themselves could be warped, or be damaged/missing/stick out from the removal of the roofing tiles, remaining nails, etc.

This means that resting the renovation package straight on the roof could be hard without removing parts of the roof or spacing out the bumps




European Regional Development Fund EUROPEAN UNIO



Roof / Reaching Heights

"Verrijker" crane




Roof / Reaching Heights




Triangle platform









Roof / horizontal segemented





Roof / end result











Contemporary upgrading by playing with windows

Option to create better climate control and comfort.



Showcases





EUROPEAN UNION

uropean Regional Development Fund

Conditions showcases Domijn

General principles for productdesign

- 3 different properties as a showcase in the same row.
- Performance based design principles
- Prototype budget excluding any special circumstances (i.e. asbestos removal)
- Renovation in an inhabited state



Selection of potential assets

- Year of construction between 1965-1974
- End of economic life > 2050
- Sales objective and strategy
- Complete housing blocks for efficiency reasons



Terraced



Semi-detached



Appartement





Showcase Domijn

- Location selected
- Challenging showcase to show opportunity's
- Preparations are started, Realization Q4 2020
- Multiple goals



Timescale

All LOIs should be signed before 1st quarter 2020

GROUP 1 - Netherlands/Belgium

- Proposal Stage in 2nd quarter 2020
- Manufacturing Stage in 4th quarter 2020
- Showcases finished in 4th quarter 2020

GROUP 2 – UK/Sweden/Norway/Germany

- Proposal Stage in 3rd quarter 2020
- Manufacturing Stage in 1st quarter 2021
- Showcases finished in 1st quarter 2021



Next steps



Main steps in the project

- 1. Assessment of the housing stock
- 2. Development of the renovation packages
- 3. Development of the factory blueprint
- 4. VR and AR visualization
- 5. Showcases



Next external webinar

- When: Thursday 28 november, 14.00 tot 15.00 uur (CET!)
- Theme: Integration in the production process/the digital factory
- Presented by: Arjan de Haan & Lianda Sjerps
- Registration: at the website INDU-ZERO



Take home message

Industrial Net Zero renovations for half the current price!

- https://northsearegion.eu/indu-zero/
- ➤ INDU-ZERO newsletter
- **>** Webinars
- **≻**Reports

